BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18319/CALL-2

APPROVED SCHEDULE - B

EE/TP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Development and removal of overburden earth in CQAL layout park in ward no. 8, kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K ANIL KUMAR		
				In Figures		In Words
1	5760	Clearing and grubbing land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm by manual means in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials, labour charges compelte as per specifications.	cum	5.6	32256.00	Rupees Five and Sixty Paise Only
2	6048	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications	Cum	145.0	876960.00	Rupees One Hundred Forty Five Only
3	6048	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	cum	72.0	435456.00	Rupees Seventy Two Only
					1344672.00	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

26/2